Northwind Solar Farm - Project Brief (revised May 2026)

This brief summarises the Northwind Solar Farm project for the steering committee.

The project is sponsored by the Halden County Energy Cooperative.

The site is located 12 kilometres north of the town of Marlow.

2. Capacity and technology

The farm will have an installed capacity of 48 megawatts.

It will use 96,000 bifacial panels mounted on single-axis trackers.

Expected annual generation is 82 gigawatt-hours.

3. Budget

The total capital budget is 44.0 million euros.

The steering committee approved the revised budget on 12 May 2026.

A contingency reserve of 3.6 million euros is included in the total.

4. Schedule

Construction is planned to start in September 2026.

Grid connection is targeted for the fourth quarter of 2027.

The main construction contractor is Brightline Builders.

5. Environment

A 15-metre hedgerow buffer will surround the site to protect local wildlife.

Sheep grazing will be used to manage vegetation between panel rows.

6. Community

Residents of Marlow will receive a 10 percent discount on electricity tariffs.

A community fund will receive 50,000 euros per year from project revenue.